6. Bill of Quantity

SCOPE OF WORK WATER PROOFING WORKS AT ADAMJEE BUILDING

(ONE JOB)

	Retro-fitting of Water Proofing at Adamjee A	cadem	ic Building at	t IBA Main C	ampus Karachi
S. No	Description	Unit	Rate	Quantity	Amount
1	Cutting, making rough Chamfer 3"x3" in Triangular at wall and roof joint all along the sides of the building and making Chamfer 3"x3" using Concrete 1:1-1/2:3 using 3/8" down crush including curing etc. complete.	Rft	22/	1800	39,600/
2	PROVIDING &APPLYING EXPAN COTE RUBBER -FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D- 543 AND ASTM C-907. as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding, lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.	SFT	MEMBER (EXTERN	10,000	650,000/-

TOTAL AMOUNT

Admin Officer CEMBIVOLO

Total Amount is Words: Rupees:

KAM KHANI CONSTRUCTION & BUILDERS

PPRA Advisor HEJ

& Manager 17 IBA, Kaxaeli

Stamp & Signature

Page 15 of 24

Proprietor

WATER PROOFING WORKS AT TABBA BUILDING

(ONE JOB)

Retro-fitting Of Water Proofing At Tabba Academic Building At IBA Main Campus Karachi S. No Description Unit Rate Quantity Amount Cutting, making rough Chamfer 3"x3" in Triangular at wall and roof joint all along the sides of the building and making Chamfer 3"x3" using Concrete 1:1-1/2:3 using 3/8" down crush including curing etc. complete. PROVIDING &APPLYING EXPAN COTE RUBBER - FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D - 543 AND ASTM C-907 . as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding , lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete. TOTAL AMOUNT										
Cutting, making rough Chamfer 3"x3" in Triangular at wall and roof joint all along the sides of the building and making Chamfer 3"x3" using Concrete 1:1-1/2:3 using 3/8" down crush including curing etc. complete. PROVIDING &APPLYING EXPAN COTE RUBBER - FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D- 543 AND ASTM C-907. as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding, lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.		R	Retro-fitting Of Water Proofing At Tabba Academic Building At IBA Main Campus Karachi							
Triangular at wall and roof joint all along the sides of the building and making Chamfer 3"x3" using Concrete 1:1-1/2:3 using 3/8" down crush including curing etc. complete. PROVIDING &APPLYING EXPAN COTE RUBBER - FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D- 543 AND ASTM C-907 . as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding , lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.		S. No	Description	Unit	Rate	Quantity	Amount			
FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D- 543 AND ASTM C- 907. as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding, lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.		1	Triangular at wall and roof joint all along the sides of the building and making Chamfer 3"x3" using Concrete 1:1-1/2:3 using 3/8" down	Rft	22/	1500	73,000/			
TOTAL AMOUNT	AIRPERSON PURCHASE CÔME BUSINESS ADMINIS KAR CARRAL Chaiperson IBA, Vonta	MITTEE TRATION	FLEX MANFACTURED BY FOS PAK CONFIRMING TO ASTM D- 543 AND ASTM C- 907. as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: ExpanCOTE* Rubber-flex should be applied by brush, roller, trowel or spray (Two coats application on horizontal surfaces) at a minimum wet film thickness of 1.0 mm On a vertical surface a film build of 1.5 – 2.50 mm is achievable in two to three coats with reinforced polyester sheet. This rate is inclusive of all type of labour, material, tools & plants, Scaffolding, lifting etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.	SFT	65/-	11500				
			TOTAL AMOUNT	_			780,00			

Total Amount is Words: Rupees: Seven Lakh

Grand Total Amount of Adamjee & Tabba Building

Rs. 1470,100/-

Grand Total Amount in Words:

& BUILDERS

MEMBERGEXTERNI CENTRAL PURCHASE COMMITTEE ASTITUTE OF BUSINESS ABNUMISTRATION

CHAIRPERS CENTRAL PURCHASE CO

Cheris Courtshi HES
PPRA Advisor HES

COMMITTEE St-Manager I IBA, Leaxachi

Proprietor

Stamp & Signature

Page 16 of 24

MEMBER BUSINESS ADMINISTRATION Syed Alebora Hessain Korsnie