

# Institute of Business Administration (IBA)

## Main Campus

Project : House No.B-05 (Staff Town)

Works : Repair & Maintenance Works

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><b><u>Porcelain Tile ( 24"x24"</u></b> Supply and lay homogenized full body porcelain tiles of required size &amp; colours of prime quality of Master/Shabbir or approved equivalent sample, set with cement slurry including filling and grouting the joints with white cement and matching pigments, complete in all respect as per drawing and as directed by the Engineer.</p>		
a	On Floor:- With upto 3" thick setting bed in (1:4) mortar.	390.0	Sft.
b	On Dado / Skirting :- with 20mm thick rough plaster in (1:4).	45.0	Sft.
	<p>NOTE: -As per attached BOQ. -Site Visit is mandatory before submission of quotation. -SST 13% will charge</p>		