

**6. Bill of Quantity****Renovation of Bathroom and Sewerage Line at IBA City Campus**

S. No.	Description	Area	Unit	Rate	Amount
1	Excavation for Foundations to the required depth 2ft including ramp side depth of 6ft in all kinds of soil dry or wet, hard, average or soft including dewatering and shoring if required and all operations of backfilling soil in 150 mm thick layers wherever required within the specified depth and disposal of excess material at designated places. Complete in all respects as directed by the owner's representative / maintenance department.	1140	Sft	60	68,400/-
2	Providing and laying screed concrete 1:2:4 thickness 2ft over UPVC pipe as per specifications and instructions of the engineer in-charge or according to the specification as approved by the / maintenance department.	1140	Sft	129	147,060/-
3	Providing and laying ceramic wall tiles of approved make & shade in dado and skirting including jointing and washing the tiles with white cement slurry, with matching color pigment, including curing and cleaning etc complete in all respects as directed by the engineer incharge or according to the specification as approved by the maintenance department.	2	Nos	14000	28000/-
4	Providing and laying UPVC pipe of 8 inch dia sch 40 specifications maintaining slope for drainage complete in all respect as per maintenance department.	290	Rft	1490	432,100/-
5	Dismantling and disposing of and removal of debris from the site and it's disposal as required by the client.	2	Nos	15000/-	30000/-
i	i-Existing Floor Tile				
ii	ii- Commode And Wall Tiles Behind Commode Area				
Total Amount					705,560/-
SST				13%	91,772.8
Grand Total Amount Inclusive of Taxes					797,332.8

Grand Total Amount Inclusive of Taxes Rupees in Words: Rs. Seven

lacs ninty seven thousand  
Three hundred thirty two /-

Rs 797,332.8

I.K. Enterprises & Co  
Stamp & Signature



DR. SHANID MIR  
Page 14 of 22 Jan - PC  
Assistant Professor - Management

Syed Akbar Husain  
Manager Finance (Payable)  
IBA City Campus

M. HARI QURESHI  
External Member - PC  
Academic Specialist - HEI  
University of Karachi