Comparative Statement
Provide, Supply & Fixing of Carpets at G&T Auditorium
Tender#CW/17/26-27

S #	Description	UOM	Qty	Estimate				M/s. Taheri Supply Agency				M/s. Al-Dost Engineering Services			
				Material		Service Charges		Material		Service Charges		Material		Service Charges	
				Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
1	**Carpet Tile 2x2**														
	Providing and laying approved carpet flooring complete with adhesive/ underlay as applicable, cutting, jointing, edge finishing, transition strips and all accessories, complete as per approved sample. - Brand: Milliken or Anker - TILE ANKER or OFC – STRATUM/ SUNSHI/ URBAN RYTHM Series - Product: Anker-OFC - Manufacturer: OFC Commercial Carpet Co., Ltd. (Anker GmbH - Fibre: 100% Resilya® Nylon 6 / Polyamide 6 - Fibre type: Solution Dyed - Construction: High-Low Loop & Tip Shear - Gauge: 1/12 - Module: 25 × 100 cm - Backing: PVC with fiberglass - Colour: Grey, exact shade/sample as approved by Architect - Fire performance: Critical Heat Flux ≥4.5 kW/m² in accordance with GB 8624-2012 - Anti-static: Walking test ≤2.0 kV in accordance with GB/T 18044-2008 - Dimensional stability: As manufacturer's tested specification - Colour fastness to rubbing: ≥4 - Colour fastness to light: ≥5 - Tuft withdrawal force: ≥24 N - Indoor air quality: GB/T 18587-2001, A Grade	Sft	2613.10	625.00	1,633,187.50			600.00	1,567,860.00			750.00	1,959,825.00	60.00	156,786.00
2	**Removal of existing carpet and Floor Preparation**														
	Carefully removing existing carpet flooring, including removal of adhesive residues, cleaning, scraping, and surface preparation of the existing floor to receive new carpet, complete in all respects as directed by the Engineer.	Sft	2557.00	75.00	191,775.00					80.00	204,560.00			30.00	76,710.00
Total					**1,824,962.50**				**1,567,860.00**		**204,560.00**		**1,959,825.00**		**233,496.00**
18% GST					328,493.25	15% SRB			282,214.80	15% SRB	30,684.00		352,768.50	15% SRB	35,024.40
Total Amount Including GST & SST									**1,850,074.80**		**235,244.00**		**2,312,593.50**		**268,520.40**
Grand total with Taxes							**2,153,455.75**				**2,085,318.80**				**2,581,113.90**

Muhammad Anwar	Syed Akbar Hussain Kazmi	Muhammad Haris Qureshi	Sadia Jabeen Asim	Muhammad Rameez
Chairperson PC-A	Member PC-A	External Member PC-A	External Member PC-A	Member PC-A
Chief Librarian, IBA Karachi	Manager Finance, IBA Karachi	Procurement Specialist, HEJ	Senior Engineer (Civil), HEJ	Sr. Manager Projects, IBA Khi.