6. Bill of Quantity

SCOPE OF WORK PAINTING WORKS AT GIRLS HOSTEL

BILL OF QUANTITIES

S		T	1	1	
#	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	Distempering three renewal coats with vinyle distemper (Paintex ICI Dulux) of approved make and shade to walls and ceiling etc., including scraping cleaning the old surface in any floor.	21100	100 Sq.ft.	751.51	158,569.00
3	Repainting two coats with plastic emulsion paint of (ICI) Dulux make and shade to walls and ceiling including cleaning, and sand papering the surface as directed by the Engineer-in-charge in any floor.	66900	100 Sq.ft.	789.14	551,609.00
1	Repainting two coats with weather shield paint of (ICI) Dulux make and shade on plaster surface (External) including cleaning, sand papering the surface as directed by the Engineer-in-charge in any floor.	46000	100 Sq.ft.	505.10	232,346.00
	Repainting two coats with enamel paint (Robialac) of approved make and shade to wood work including cleaning and sand papering the surface as directed by the Engineer-in-charge in any floor.	12500	100 Sq.ft.	1,003.89	125,486.00
	French polishing two renewal coats of approved make to wood work including cleaning the old surface as directed by the Engineer-in-Charge in any floor	1050	100 Sq.ft.	1,787.25	18,766.00
BER	Applying one renewal coat with synthetic red oxide primer of approved make including scraping and sand papering the surface as directed by the Engineer-in-Charge in any floor.	4500	100 Sq.ft.	516.59	23,247.00
TOTAL AMOUNT AS PER PAK PWD SCH.OF RATES 2012			111	1,110,023/-	
ADD CONTRACTOR'S PREMIUM			Add + 27%		

Finance **Grand Total Amount**

14,09,729.21

Grand Total Amount Rupees in Words: Rs.

Note:

This rate is inclusive of all local, provincial and federal taxes & levis and no payment

in this account is permissible

CREATIVE CONTRACTORS Mabacos kha CEMB, VOK

* Against PO# 018 4/463
amount 40,000/-

Stamp & Signature

Page 14 of 23

AKIHART Professor UBA, Karachi

Sa. Managex IT IBA, Karachi