

Institute of Business Administration (IBA)

Main Campus

Project : Fixing of Wood Panel Door with Glass in iShop Container

Works : Repair & Miantenance Works

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Wooden Panel Door with Glass</u> Supply and fix in position 40 mm thick 1st class Partal wood double leaf paneled door shutter of any shape with, upto 200 mm wide style and rails, upto 20 mm thick paneling, shutter to be fixed with partal wood frame of upto 1.5 inch thick & upto 3 inch wide, 5mm thick clear glass of Ghani should installed along with necessary beeding in half of door. This item includes the cost of liquar polish to all exposed wood, termite proofing of wood and all hardware's / ironmongery of approved quality brass butt hinges, tower bolts fixed to top & bottom of closing shutter door stopper, O.H. door closer, Cylindrical Lockset etc of KHAS Brand, complete in all respect as per as shown specifications and as directed by the Engineer.</p>	64	Sft
2	<p><u>Gypsum Ceiling Tiles.</u> Supply and lay pvc laminated Gypsum ceiling tiles of DFB or equivalent of square edge, size 600 x 600 x 9mm thick in approved surface designs and textures , laid into a exposed T-Bar metal system frame work suspended from the structural ceiling, complete in all respect as per drawing and specifications.</p> <p>NOTE: Site visit is mandatory before submitting the quotation. SST 13% will charge</p>	170	Sft