

INSTITUTE OF BUSINESS ADMINISTRATION (IBA) KARACHI								
IBA HOSTEL MAIN CAMPUS KARACHI.								
BILL OF QUANTITIES FOR SUPPLY, FABRICATION & ERECTION OF STAIR CASE GRILL DOOR AT IBA HOSTEL (BALANCE WORK)								
S. No.	Description	Qty	Unit	Material Rate	Material Cost	Installation Rate	Installation Cost	Total Amount
				Rs.	Rs. (3x5)	Rs.	Rs. (3x7)	Rs. (6+8)
1	2	3	4	5	6	7	8	9
A	STAIR CASE GRILL DOOR Supply,Fabrication, & Erection in position at site of Grill Door at stair average size 7'-0" x 3'-0" (6Nos)Complete as per specification. The grill comprises of 2"x1" rectangular tube frame 18 SWG thickness with intermediate pipe support of same size and two numbers round pipe 2" dia 18 SWG over angle iron frame with locking arrangements including grinding , painting with Enamel Paint in approved shade and colour and fixing in position complete as per direction.	126	SFT	0	0	0	0	0
1								
2	Supply,Fabrication, & Erection in position at site of Grill Door at Pump Room average size 10'-0" x 3'-6" (1Nos)Complete as per specification. The grill comprises of 2"x1" rectangular tube frame 18 SWG thickness with intermediate pipe support of same size and two numbers round pipe 2" dia 18 SWG over angle iron frame with locking arrangements including grinding , painting with Enamel Paint in approved shade and colour and fixing in position complete as per direction.	35	SFT	0	0	0	0	0
3	Supply,Fabrication, & Erection in position at site of Grill Bath Room average size 6'-0" x 4'-0" (2Nos)Complete as per specification. The grill comprises of 2"x1" rectangular tube frame 18 SWG thickness with intermediate pipe support of same size and including grinding , painting with Enamel Paint in approved shade and colour and fixing in position complete as per direction.	48	SFT	0	0	0	0	0
Sub-Total Carried to Summary								0
Sub-Total Carried to Summary								