

**Comparative Statement**  
**Construction of Boundary Wall of Girls Hostel**  
**Tender # CW/15/19-20**

S.#	Description	Qty	UNIT	M/s Syed Rahim Shah & Brothers		M/s Malik & Co.		M/s Al Zaman Construction Co.		M/s S.M Saeed & Brothers		M/s Hamza T Contractor & General Order Supplier	
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	Dismantling/cutting/removal of curb stone and stacking properly within I.B.A. premises as directed by Site incharge.	50	Rft	40.00	2,000.00	130.00	6,500.00	200.00	10,000.00	40.00	2,000.00	100.00	5,000.00
2	Excavation of any type of soil/strata for foundation/plinth beam with back filling with approved suitable excavated material also disposal of all surplus material out side of I.B.A. premises as directed by the Site incharge.	3500	Cft	28.00	98,000.00	17.00	59,500.00	25.00	87,500.00	130.00	455,000.00	20.00	70,000.00
3	Lean Concrete c.c. 1:4:8. using Sulfate Resisting Cement. as per instruction of site engineer av. 4" thick in foundation.	231	Cft	120.00	27,720.00	215.00	49,665.00	200.00	46,200.00	195.00	45,045.00	250.00	57,750.00
4	Providing and Laying reinforce cement concrete 1:2:4. using SR Cement in Column footing average 1'-0" thick including mixing, transporting, curing and placing in position in water tight form work including the cost of making complete in all respect and as directed by the Site incharge but excluding the cost of reinforcement.	315	Cft	225.00	70,875.00	340.00	107,100.00	350.00	110,250.00	385.00	121,275.00	650.00	204,750.00
5	Providing and Laying reinforce cement concrete 1:2:4 using SR Cement in Plinth Beam including mixing, transporting, curing and placing in position in water tight form work as directed by the Site incharge but excluding the cost of reinforcement.	526	Cft		136,760.00	350.00	184,100.00	350.00	184,100.00	385.00	202,510.00	675.00	355,050.00
6	Providing, cutting, bending and binding high tensile deformed steel reinforcement bars (60,000 Psi) conforming to ASTM 615 including the cost of binding wire, sree chairs, pins, spacers, un specified laps, Wastage etc. complete in all respect and as directed by the Site Incharge.	3000	Kg	160.00	480,000.00	152.00	456,000.00	150.00	450,000.00	160.00	480,000.00	185.00	555,000.00
7	Providing and Laying reinforce cement concrete 1:2:4 using OPC Cement in Column Super Structure including mixing, transporting, curing and placing in position in water tight form work as directed by the Site incharge but excluding the cost of reinforcement.	350	Cft	255.00	89,250.00	350.00	122,500.00	350.00	122,500.00	375.00	131,250.00	600.00	210,000.00
8	Providing and Laying 6" thick Machine Made Block Masonry 1:9 with 1:6 CSM with max. 1" thick joint with groove with proper pointing on both side upto 8'-0" above plinth level including curing, scaffolding tools etc as directed by the Site Incharge.	2800	Sft	120.00	336,000.00	130.00	364,000.00	120.00	336,000.00	65.00	182,000.00	410.00	1,148,000.00
9	Providing and Laying 1:6 CSM plaster ½" thick in true length & line & level including curing as per direction of Engineer Incharge	5600	Sft	45.00	252,000.00	37.00	207,200.00	50.00	280,000.00	65.00	364,000.00	80.00	448,000.00
10	Providing and laying lime wash in desired colour shade as per direction of Engineer Incharge.	5600	Sft	4.00	22,400.00	23.00	128,800.00	8.00	44,800.00	25.00	140,000.00	18.00	100,800.00
11	Providing and fixing hot dip galvanized angle Y-type angle Iron ¼" thick both arm minimum 2'-0" with minimum 6" embedded in column Concrete with min 5 nos double twist Barbed Wire Each wire dia 1.5mm ~2.0mm and bar spacing 5.0 Cm hot dip galvanized iron strand wire diameter 2.5mm ~ 3.0 mm fixed as directed by the Site incharge.	350	Rft	300.00	105,000.00	350.00	122,500.00	600.00	210,000.00	350.00	122,500.00	600.00	210,000.00
<b>Total Amount ( Inclusive of all taxes )</b>				<b>Rs. 1,620,005.00</b>		<b>Rs. 1,807,865.00</b>		<b>Rs. 1,881,350.00</b>		<b>Rs. 2,245,580.00</b>		<b>Rs. 3,364,350.00</b>	

MEMBER  
 CENTRAL PURCHASE COMMITTEE  
 INSTITUTE OF BUSINESS ADMINISTRATION  
 Syed Arbab Hussain Kazmi  
 Finance  
 IBA, Karachi

CHAIRPERSON  
 CENTRAL PURCHASE COMMITTEE  
 INSTITUTE OF BUSINESS ADMINISTRATION  
 DR. S.M. Farhat Iqbal  
 Assistant Professor  
 IBA, Karachi

MEMBER (EXTERNAL)  
 CENTRAL PURCHASE COMMITTEE  
 INSTITUTE OF BUSINESS ADMINISTRATION  
 H.A. Aureshi  
 PPRA Advisor  
 HES