	Institute of Business Administration (IBA) Main Campus					
BOQ for Renovation of ICT OFFICE IN CITY CAMPUS						
	DEN PARTITION & FURNITURE WORK IN CITY CAMPUS	•				
1. Item No.	2. Description of Item	3. Quantity	4. Unit			
Α	SECTION-A					
1	4'-0" Low Height Partition With MDF Table Top Providing and fixing in position 4'-0" HT. Wooden Partition work along with 16 mm thick Table top as per drawing using partal wood frame work of 1.5 inch (thick) and 2 inch wide (24" horizontally and 18" vertically) with 16 mm MDF laminated sheets of ZRK brand or Equivalent on both sides finished of approved shade and colour as shown in drawings.The sides & bottom of table top shall be covered by Partal wood frame to support. Provide 4" wide Aluminium skirting at the bottom of partition on both side.All exposed wood surfaces to be finished with wood lacquer polish and necessary beeding (3mm thick Partal Wood) of approved shades as directed including all necessary fittings/hardware and wood preservative (Termite Proofing) etc. as per list of approved material and as approved by the Engineer Incharge complete in all respects.	220.0	Sft.			
2	Removal of Existing Wooden Partitions Removal of existing shelf & cabinets in a usable condition and handed over the material to client in good condition, complete in all respect as directed by Engineer Incharge.	95.0	Sft.			
3	 Floor Mount Cupboard (6'-0"x2'-0"x8'-0") Wall Mount Cupboard Specification: Made up of 16 mm thick MDF laminated Sheet of ZRK Brand or Equivalent on top, sides, bottom, shelves, and shutters along with 1" thick x 2" wide partal wood frame 4 mm thick one side MDF laminated back sheet at the back Box-type hinges of approved make. PVC Lipping finished with melamine of approved laminate on all the shutter edges. External surfaces finished with 1mm thick Laminate of approved make 16 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc. 	48.0	Sft			

Institute of Business Administration (IBA) Main Campus BOQ for Renovation of ICT OFFICE IN CITY CAMPUS WOODEN PARTITION & FURNITURE WORK IN CITY CAMPUS									
						1. Item No.	2. Description of Item	3. Quantity	4. Unit
						4	 Wall Mount Cupboard (27'-6" x 2'-6" x 1'-2") Cabinet Specification: Made up of 16 mm thick MDF laminated Sheet of approved shade of ZRK Brand or equivalent. on top, sides, bottom, shelves, shutters and drawer along with 1" thick x 2" wide partal wood frame . 4 mm thick one side MDF laminared sheet at the back. Box-type hinges of approved make. PVC Lipping finished with melamine of approved laminate on all the shutter edges. External surfaces finished with 1mm thick Laminate of approved make 16 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc. NOTE: Site Visit is mandatory before submission of quotation. IBA Main Campus Maintenance Dept. -SST 15% will charge 	70.0	Sft