

# Institute of Business Administration (IBA)

## Main Campus

### BOQ for Renovation of FINANCE IN MAIN CAMPUS

#### WOODEN PARTITION & FURNITURE WORK IN MAIN CAMPUS

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><b><u>3'-0" Low Height Partition With MDF Table Top</u></b></p> <p>Providing and fixing in position 3'-0" HT. Wooden Partition work along with 16 mm thick Table top as per drawing using partial wood frame work of 1.5 inch ( thick) and 2 inch wide (24" horizontally and 18" vertically) with 16 mm MDF laminated sheets of ZRK brand or Equivalent on both sides finished of approved shade and colour as shown in drawings. The sides &amp; bottom of table top shall be covered by Partial wood frame to support. Provide 4" wide Aluminium skirting at the bottom of partition on both side. All exposed wood surfaces to be finished with wood lacquer polish and necessary beeding (3mm thick Partial Wood) of approved shades as directed including all necessary fittings/hardware and wood preservative (Termite Proofing) etc. as per list of approved material and as approved by the Engineer Incharge complete in all respects.</p> <p>As per drawings</p>	90.0	Sft.
2	<p><b><u>3'-0" Low Height Partition With MDF Table Top</u></b></p> <p>Providing and fixing in position 3'-0" HT. Wooden Partition work along with 16 mm thick Table top as per drawing using partial wood frame work of 1.5 inch ( thick) and 2 inch wide (24" horizontally and 18" vertically) with 16 mm MDF laminated sheets of ZRK brand or Equivalent on both sides finished of approved shade and colour as shown in drawings. The sides &amp; bottom of table top shall be covered by Partial wood frame to support. Provide 4" wide Aluminium skirting at the bottom of partition on both side. All exposed wood surfaces to be finished with wood lacquer polish and necessary beeding (3mm thick Partial Wood) of approved shades as directed including all necessary fittings/hardware and wood preservative (Termite Proofing) etc. as per list of approved material and as approved by the Engineer Incharge complete in all respects.</p> <p>4 Caster Wheels Shall be placed. Sample is required for quality approval</p> <p><b>NOTE:</b> -Site Visit is mandatory before submission of quotation. -SST 15% will charge</p>	20.0	Sft.