



INSTITUTE OF BUSINESS ADMINISTRATION, KARACHI

BILL OF QUANTITIES FOR FALSE CEILING AT IBA GIRLS' HOSTEL

B.O.Q Item	Description	Unit	Quantity
1	False Ceiling Supply and lay PVC laminated Gypsum ceiling tiles (make United Gypsum or Equivalent) of square edge, size: 600 x 600 mm in approved surface designs and textures, laid into an exposed T-Bar metal system frame work and necessary supports at every 4'-0" span suspended from the structural ceiling. False ceiling to be fixed at the height of 12'-0" including scaffolding and other required arrangements, complete in all respect. NOTE: -Protection of the existing floor is the Contractor's responsibility. -False ceiling materials shall be approved before commencement of work. -Site Visit is mandatory before submission of quotation. -SST applicable rates will be charged on works.	SQFT	1,956.00