Comparative Staement
Installation of Sill Batta Stone Cladding at Faculty Apartment (Block C&D) IBA Staff Town
Tender # CW/14/26-27

B.O.Q Item	Description	Unit	Quantity	Engineer's Estimate		M/s. Teknix Engineering Company		M/s. I.K. Enterprises & Co.		M/s. Allied Logistics Company		M/s. Al-Dost Engineering Services	
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	**Removal of Existing External Paint**												
	Removal of existing paints from walls, column and etc using cup grinder to obtain a base plastered surface including cordon off the working area with plastic sheet/green nets and dispose of the waste material outside the premises, complete in all respect as directed by Engineer in charge.	P.sft	2710.50		-	50.00	135,525.00	10.00	27,105.00	49.00	132,814.50	40.00	108,420.00
2	**Installation of Sill batta (Basalt Rock)**												
	Installation of silbatta Basalt Stone (rough surface) wall cladding (3/4 inch thick) as per sample shown with alternate layers of 8"x12" and 2"x12" of approved pattern with requires thickness of tile bond of Ressichem TA Re Bond 245 or with mechanical anchors (where required). The scope of work includes the supply of all materials, stacking and cutting at designated location, dressing, ; ensuring proper alignment, level, and joint uniformity; filling and pointing of joints with colored mortar; curing, and finishing of the cladded surface.	P.Sft	2710.50		-	377.00	1,021,858.50	417.00	1,130,278.50	386.00	1,046,253.00	412.00	1,116,726.00
	TOTAL ESTIMATED AMOUNT (FOR BLOCK C & D)		PKR		-		1,157,383.50		1,157,383.50		1,179,067.50		1,225,146.00
	ADD SST @ 8 %		PKR		-		92,590.68		92,590.68		94,325.40		98,011.68
	TOTAL ESTIMATED AMOUNT (INCL. SST)		PKR		1,595,400.00		1,249,974.18		1,249,974.18		1,273,392.90		1,323,157.68
	ADD SST @ 8 %								1,249,977.78				

Muhammad Anwar	Syed Akbar Hussain Kazmi	Muhammad Haris Qureshi	Sadia Jabeen Asim	Muhammad Rameez
Chairperson PC-A	Member PC-A	External Member PC-A	External Member PC-A	Member PC-A
Chief Librarian, IBA Karachi	Manager Finance, IBA Karachi	Procurement Specialist, HEJ	Senior Engineer (Civil), HEJ	Sr. Manager Projects, IBA Khi.