

Institute of Business Administration (IBA)

Main Campus

Project: AMAN CED IBA, Main Campus

Works: Fixing of Aluminium Window & Fix Partition

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Making of Window Opening in AMAN CED Building</u></p> <p>a Removal of existing 12mm sandwich tempered glass of size (30" x 116") from the front elevation cladding with the help of erection of MS folding pipe with due care and the glasses shall be handed over to the client in good condition.</p> <p>b Supply and fix in position as specified anodized aluminum works as specified in silver colour of Pakistan cable or Equivalent with best quality tempered glass of Ghani Glass or Equivalent and all imported iron mongery & fillings, of approved quality. This item includes mastic sealant to joints between the building openings and frames, complete in all respect as per drawings and specification.</p> <p>i <u>2'-6" x 4'-0" Openable window with 8mm thick brown tempered glass along with openable mosquito net frame.</u> (Note: Upto 50x75 mm, box section (1.6 mm thick), having item code No.7001 M, 70040 & 7008, shall be used)</p> <p>ii <u>2'-6" x 5'-8" Fix glazing partitions with 8 mm tempered glass along with aluminium beeding & glass fixing system.</u> (Note:Upto 50x75mm (Approx). Box section (2.0mm thick), having item code No.70018, 70014, 70015 & 70016 shall be used.</p> <p>Note: -The above job is work at height in nature and requires proper attention.Site Visit is mandatory for proper understanding of work & quotation of rates. -SST 15% will charge</p>	2	No.s