

## BOQ\_Cleaning of 826.22kWp Solar System at IBA Main Campus

Sr No	Product	Unit	Qty
1	<p>Cleaning of 826.22kWp On grid Elevated Bus port &amp; Car port Solar Panels as per manufacturer's manual with approved material, 2 times in a month after 15 days of interval.</p> <p>PV Modules:545Wp Mono PERC Half-Cell Crystalline PV Module Brand: Jinko Total Numbers of PV Modules Qty=1516</p> <p>Notes:</p> <p>i)The cleaning of the solar panels should not include any abrasives or chemicals. The only permissible cleaning supplies are air, water, and microfiber cloths (as specified by the manufacturer).</p> <p>ii)The Contractor will provide labor and labor supervision and furnish approved material and services to wash clean solar panels at the subject site.</p> <p>iii)Water,electricity &amp; Ladder/Scaffolding will be provided by IBA.</p> <p>iv)Any damage to the arrays or PV Modules caused by the cleaning contractor are the responsibility of the contractor to repair or to replace with new of same make/model and specifications.</p>	Each	2