

Institute of Business Administration (IBA)

Main Campus

Project : House No.B-05 (Staff Town)

Works : Repair & Maintenance Works

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Wood, Plastics and Composites - 06</u> <u>Kitchen Cabinets.</u> Supply and fixing cabinets according to the size and dimensions as per site condition , made with 16mm thick MDF Laminated Sheet of ZRK Brand or Equivalent for front shutter and MDF Laminated sheet for inside shelves & Sides,5 mm thick back ply, 2" x1" thick partal wood frame and 1mm thick PVC lipping of approved colors including horizontal or vertical partition in inside, drawers & channel with handles of KHAS or Equivalent, fixing cabinets to wall with expansion bolts of 10 mm diameter at 600 c/c and all relevant hardware i.e. piano hinges, locking arrangement, handles, painting and polishing etc complete in all respect as shown on drawing specification and as directed by the Engineer. <i>(Note: Sample to be approved by Client prior to start of work.)</i></p>		
a	Wall Hung Cabinet.	75.0	Sft
b	Base Cabinets	40.0	Sft
	<p>This item includes the removal of existing cabinets.</p> <p>NOTE: -As per attached BOQ. -Site Visit is mandatory before submission of quotation. -SST 13% will charge</p>		