

BILL OF QUANTITIES (BOQ)

Project: Aman Tower & JS Auditorium

Location: Basement Area

Nature of Works: Drainage & Cleaning, Civil Repair & Metal/Iron Works

S/N	Description of Works	Unit	Qty	Rate (PKR)	Amount (PKR)
1	Opening and cleaning of choked drainage pipelines using mechanical drain cleaning machine, including all tools, equipment, and labor, complete in all respects	Job	1		
2	Cleaning of trench including removal of soil, debris, stones, roots, and waste materials; repairing and finishing with cement plaster to required line and level, complete in all respects	Job	1		
3	Repair, surface preparation, and painting of existing MS grating, including removal of rust, straightening and repair of damaged portions, application of one coat of approved primer and two coats of approved enamel paint, complete in all respects	Job	1		
	GRAND TOTAL				