

6. Bill of Quantity

SCOPE OF WORK

S #	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Dismantling the existing fixed M.S. sheet by cutting, with due care including folding, planks grinder disc ect and protection the glass and aluminum frame existing their, all tools plants cost should be included into the rate. All MS sheet would be handed over to IBA. Complete the job in all respect.	SFT	264	150	39,600
2	Providing and fixing in position 2"x2"x2"" thick angle Iron frame plus 2"x2" x 2"" thick flat strip at mid points of the frame welded with existing MS Columns at both edges inclusive of all tools plants folding welding machine rods, folding and planks etc. Application of red oxide paint be made over newly fixed frame 2" x 2" x 2"" thick flat strip	sft	264	1020	269,280
3	providing and fixing Expanded Metal/MS Jali 1/2" jali, welded it all around with angle iron frame inclusive of, all tools , plants welding's folding and planks complete in all respect and as per IBA Engineer satisfaction.	sft	264	250	66,000
4	providing and fixing 1/2" thick ply at the back of framing which would used as a shuttering joint with frame with ply by cut screws. All tools plants , folding and planks also included , Complete in all respect as per the instruction of Engineer	sft	264	110	29,040

Osama A. Rayoom
External Member

[Signature]
M. Hanif Member

[Signature]
Shahab ud din Khan
(Member)

Stamp & Signature

Mansoor Ali
Member.



[Signature]
17/06/2022
M. Naveed Akhter
External Member

[Signature]
Mudassar Baig
Member
Muhammed Anwar
Chairperson
17/6

5	Providing and Fixing 1:2:4 concrete using 0 to 5 no. crush chips about 1.5" thick concrete would be placed, all tools, plants folding curing etc would include in this item rate, complete in all respect as instruction of Engineer.	sft	264	200	52800
6	Providing and Placing 1:4 plaster 1" thick over the newly placed concrete using SBR in niro to joint old and new concrete, all tools plants folding curing etc. included into it.	sft	264	150	39600
7	Providing and laying 03 coat of weather shield paints ICI, Nippon or equivalent as existing colour and texture all tools plants will be included	sft	396	86	34056
Total				530376	
13% SST				68949	
Total Amount				599324	

Total Amount Rupees (in words) Five Hundred Ninety nine

Thousand Three Hundred Twenty four Rupees only

Janif
Muhammed Hanif
Member

Mansoor Akhtar
Mansoor Akhtar
Member

Osama A. Rajwan
Osama A. Rajwan
External Member

Mirza Mudassar Baig
Mirza Mudassar Baig
Member

Muhammed Naveed Akhtar
Muhammed Naveed Akhtar
External Member
17/06/2022

Muhammad Anwar
Muhammad Anwar
Chairperson

Stamp & Signature

Shahab Uddin Khan
Shahab Uddin Khan
Member