6. Bill of Quantity

SCOPE OF WORK

ROOF WATER PROOFING AT SEMINAR HALL AT IBA AMAN CENTER 12TH FLOOR INSTITUT OF BUSINESS ADMINISTRATION KARACHI

ABSTRACT OF COST

S. No	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE	AMOUNT
	SEMINAR HALLS 2 NOS EACH 10.400 2	X10.600 meter	. Total ro	of area = 2	2500 SFT
1	Removal of the existing screed including, dismantling, brooming & shifting of the debrise and disposal outside of the IBA premises complete.	2500	Per Sft	65/2	16250/=
2	Providing and applying adhesive coat ZSAC-10 / 15 of ZAHABIA chemical or equivalent complete as per manufacturer's specifications and instruction, and approval of architect.	2500	Per Sft	85/2	21250/
3	1:1-1/2:3 screed in required slope minimum 2" thick including curing, making ridges, valleys, chamfered edges, hacking of existing surface for bond where necessary etc. laid in panels not exceeding 100 Sft using 5mm thick glass strip as panel divider. The cost include the glass patti cost also.	2500	Per Sft	195/=	487500/
Total					862500/=
Prevailing SST					112125/
Total Amount with SST					974625

Grand Total Amount in Words Rupees: Nuc lace

Note:

For any confusion / query kindly contact:

Manager Building Aman Tower, IBA City Campus

TRAL PURCHASE COMMITTEE LESS ADMINISTRATION PPRA Adursor

CHAIRPERSON CEXTRAL PURCHASE COMMITTEE

Stamp & Signature KARACH Tradut

ASSISTANT Professor

Page 14 of 16 IRA /Karachi

syed Akbai H ivonce IBA, Kovach

CENTRAL PL

INSTITUTE OF E

MBER HASE COMMITTEE