

5.

Scope of Work / BoQ**Aluminum Works at Library**

S. #	Description	Quantity	Rates	Amount (Rupees)
1	MAIN STUDY AREA Providing & Installing 12mm thick tempered glass curtain free standing wall to enclose study area into a silence zone at Ground Floor (Average area 50'-0"x12.5'-0") TOTAL PERIPHERIAL LENGTH ABOUT 134 RFT. Average height of the wall is 7'-0". The work includes providing & fixing at floor Aluminum / Stainless steel Base Shoe size 4-3/16"x2-11/16 confirming to ASTM B221 fixed with anchor bolt and gasket retention grooves secures the rubber gasket in the base shoe and having glass door opening detailed as per drawing sketch attached . Complete as per instruction & repairing of the False Ceiling of Gypsum Board and cladding fixed on the columns. The vendor is requested to visit the site and submit the shop drawing along with the bid. The cost is inclusive of all fixing arrangements , hinges, handles etc complete.	938 SFT	1200	1,125,600
2	CEILING WORK Removal/cutting of existing false ceiling where necessary and Providing and Fixing new 2'x 2'x gypsum false ceiling, including G.I Suspension system complete in all respect as per instruction of Engineer	125 SFT	140	17,500
Total Amount Inclusive of all Taxes				1,143,100 1,143,100

Note:

- The Contractor is required to submit the work Schedule based on such a criteria to create a least disturbance and noise during the library working hours.
- The rate is inclusive of all type of taxes

Total Amount in Words: Rs. One Million one hundredforty-three thousand and one hundred only

MEMBER
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
Syed Akbar Hussain Kori
Finance
IBA, Karachi

CHAIRPERSON
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
DR. S. M. KARACHI
Assistant Professor
IBA, Karachi

MEMBER (EXTERNAL)
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
Harris Chyreshi
PPRA Advisor
HES



Stamp & Signature

Page 14 of 19