

**Comparative Statement**

**Laying 2" Dia Domestic Connection From KWSB Line to IBA staff Town**


**Tender # CW/07/24-25**

S. #	Items	Unit	Qty	M/s Creative Contractors		M/s Syed Rahim Shah & Brothers		M/s Shahzad Shaikh & Sons		M/s Prime Flagship	
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	Excavation for water supply lines in trenches, and pit in any type of soils clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint. Holes and disposal of surplus earth within a one chain as directed by Engineer in charge Providing fence guards, lights where ever required lift up to 10 to 12ft (3 to 4 m).	Cft	8000	120.00	960,000.00						
2	Providing & fixing M.S flange made of M.S plate, having a thickness and total weight as mentioned against each item it includes the cost of making holes, facing, welding, nuts, bolts, rubber pacing, whitelead, fitter, cartage etc. complete 2" .....Weight (2.020). The material shall be approved and as per standard of KWSB.	Each	11.00	75,000.00	825,000.00						
3	Providing laying & , finishing in trenches i.c lifting, jointing & testing etc. complete in all respect, the high density polyethylene P.E pipe (HDPE-100) conforming to ISO 4427/BIN8074/8075-BS3580 & PSI-3051 PN-12N (2" dia). This rate also include all the testing & commissioning as per KWSB.	Rft	200.00	6,000.00	1,200,000.00						
4	Kitz Company (JAPAN) Gates Wall S.S heavy pattern (Test pressure 21.0 kg/Sq.cm or 300 lb/sq.inch) 2" dia	Each	3.00	150,000.00	450,000.00						
5	Kitz Company (JAPAN) Check Wall S.S heavy pattern (Test pressure 21.0 kg/Sq.cm or 300 lb/sq.inch) 2" dia	Each	2.00	150,000.00	300,000.00						
6	Kitz Company 2" dia strainer valve	Each	1.00	150,000.00	150,000.00						
7	Construction of R.C.C Chamber cover and frame 6" thick R.C.C walls set in 1:6 C.M 6" thick C.C. 1:4:8 in foundation, 2" thick C.C. 1:2:4 flooring ½" thick cement plaster 1:6 to all inside wall surfaces, top and bottom outer side RRC wall surface 6" deep up to roof RRC i/c. M.S. foot rest 5/8" dia bars every 2'-0" deep, curing, excavation, dewatering, re-filling, etc. complete 10 X 6 X 10 (Inside Dimensions) and roof 10 X 6	Each	1.00	50,000.00	50,000.00						
8	Water Meter Kitz Company 2" dia Fixing nuts, bolts , rubber sheets ,	Each	1.00	50,000.00	50,000.00						
9	Providing & fixing M.S Spilt Collar and TEE on PRCC Pipe of different sizes having wide as mentioned against each items, to suit the size of connection, fabricated with ½ thick M.S plate excluding the cost of neck its including's the cost of 1" thick M.S flange, either a total weight as mentioned against each items it also includes the cost nuts & bolts, rubber packing, labor and sealing material and all the tools and plants, etc. complete. 33" X 33" (Weight 338.390) 3'-6"	Each	1.00	65,000.00	65,000.00						
10	Providing & fixing 0-9" long – 3/8" thick M.S Neck to existing M.S pipe or to a split collar tee having a total weight as mentioned against each item. It includes the cost of fabrication and welding to the split collar tee. 2" Weight (4.773)	Each	1.00	75,000.00	75,000.00						
11	D Watering Expense Petrol labors and Pump Rent	Each	4.00	50,000.00	200,000.00						
12	Supply and filling sand under floor and plugging in walls etc, complete in all respect, as per specifications & relevant drawings and all works to the entire satisfaction of the Engineer, (Sand Bending).	Sqft	8000.00	100.00	800,000.00						
13	Refilling the excavated in trenches 10" X 200 thick Layer i.c watering i/c rramming to full compacting etc complete (ProvisionalQuantity	Sqft	8000.00	20.00	160,000.00						
<b>TOTAL AMOUNT</b>				5,285,000.00							
<b>ADD 15% SRB</b>				792,750.00							
<b>GRAND TOTAL AMOUNT</b>				<b>6,077,750.00</b>							


Rejected, due to non-compliance of mandatory site visit

Rejected, due to JV not allowed

Rejected, due to bid security not submitted

  
**M. HARIS QURESHI**  
 External Member - PC  
 Procurement Specialist - HEJ  
 University of Karachi

  
**DR. SHAHID MIR**  
 Chairman - PC  
 Assistant Professor - Management  
 IBA Karachi

  
**Syed Akbar Hussain Kazmi**  
 Member - PC  
 Manager Finance (Payable)  
 IBA Karachi