

Institute of Business Administration (IBA)**Main Campus****Project: Redesign of Procurement Department**

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p>Gypsum Board Ceiling with Paint Finish.</p> <p>Provide and install in position Gypsum Board Ceiling MAKE: Elephant or Equivalent, consisting of G.I. framework of approved sections with G.I. Hangers and 16 SWG. aluminum edgings, 12mm thick Gypsum Board Sheet fixed on frame, with approved Paint Finish, G.I. Angle, cutting of opening for light fixtures with making of light pelmet, fiber tape on joints, metal tape edges, including primer coat, filling, and 2 coats of matt enamel paint ICI, BERGER or Equivalent. This item also includes providing and installing access panels wherever required and all other hardware, wastage, scaffolding, making access panels (where required), etc., complete in all respects.</p> <p>For payment exposed sheet surface area will be measured.</p> <p>Note: This item also includes the removal of the existing suspension system. Site visit is mandatory for quotation.</p>	720.0	sft