



INSTITUTE OF BUSINESS ADMINISTRATION, KARACHI

CEE Hall Electrical Work. SUPPLY, INSTALLATION, TESTING & COMMISSIONING, & WIRING ACCESSORIES

B.O.Q Item	Description	Unit	Quantity	Rate	Amount
1	Wiring of light circuit from DB to switch single core PVC insulated 3 x 1C - 2.5 sq.mm wire in 25mm dia PVC conduit complete in all respect. Make: Pakistan Cable/Fast Cable/Newage	Nos	1.00		
2	Wiring from switch to first light point with 2 x 1C - 2.5 sq.mm wires with pvc connector in the existing cable/PVC conduit as per site requirement complete in all respect. Make: Pakistan Cable/Fast Cable/Newage	Nos	4.00		
3	Wiring from point to point with 2 x 1C - 1.5 sq.mm wires with pvc connector in the existing cable tray/ PVC conduit as per site requirement complete in all respect. Make: Pakistan Cable/Fast Cable/Newage	Nos	4.00		
4	4 - Gang . (1-way) Make: Schnieder/Clipsal or Equivalent	Nos	1.00		
5	3x3 PVC Back Box Make: Adamjee/Pak Arab/ Clipsal/Riva	Nos	1.00		
6	4-Way Junction Box Make: Adamjee/Pak Arab/Clipsal/Riva	Nos	30.00		
7	1" Dia PVC Electrical Conduit along with complete fitting as per site requirement. Make: Jeddah/Dadex/Pak Arab/Steelex	M	80.00		
8	Led Light Round shape, Dia 2'; 36 Watt; Customised ceiling hanging/suspended Circular Ring Design LED Light minimum (2ft Dia) with extrude aluminium housing with stainless clips along with suspension kit in 4000/5000K min 36W/m. Minimum hanging length should be 2' as per site requirement complete in all respects. Make: Philips/Osram/Unilux/Coarts/Electricore	Each	8.00		
	Total				
	GST 18% for Supplies				
	SST 15% for Electrical Installation				
	Grand Total with Taxes				