

6. Bill of QuantitySCOPE OF WORKWaterproofing Works in Old Boys Hostel

S #	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	<u>Cleaning of Roof</u> Cleaning of Roof including repairing of cracks in existing roof screed by using FOS Pak Primer or equivalent putty /Creak treatment as per manufacturers direction & recommendation complete and disposal of the debris at designated place outside the IBA premises.	25,988	Sft	5 1/2	129,940 1/2
2	<u>Roof Treatment By EXPAN BRUSH RFX BY FOSPAK or equivalent</u> Providing applying Elastomeric cementitious waterproofing coating Expanbrush* or equivalent RFX manufactured by FOSPAK or equivalent as approved in two coats. Total dry film thickness should not be less than 1.5mm. The material is to be applied as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: EXPANBRUSH RFX* or equivalent acrylic polymer modified Cementous water proof coating should be applied by brush, roller, trowel or spray in two coats application on horizontal surfaces at a minimum wet film thickness of 1.0 mm as first coat and 1.5mm thickness of the second coat the minimum dry film thickness should not be less than 1.5mm Spalled and deeply disintegrated concrete should be removed to sound concrete and repaired with a Expanchem Fospak or equivalent repair system, This rate is inclusive of all type of labour, material, tools & plants, Scaffolding , lifting, testing of surface as per prescribed etc. This rate is also inclusive of all type of federal, provincial and municipal taxes etc. complete.	25,988	Sft	51 1/2	1,325,388 1/2
3	<u>Making of 6" x 6" P.C.C Chamfer</u> Providing & making, Cutting making rough chamfer 6" x 6" in triangular at wall and roof junctions or openings all along the sides of the building and making Chamfer 6" x 6" using concrete ratio 1: 2 :4 having (10 mm) down crush including using of S.B.R with proper binding, curing etc complete in all respect as directed by Engineer Incharge.	1,968	Rft	35 1/2	68,880 1/2

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

M. HARIS QURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi

DR. SHAHID MIR
Chairman - PC
Assistant Professor Management
IBA Karachi

Stamp & Signature

Page 14 of 23



4	PreCast Rain Water Spout Providing and fixing Plain Cement Concrete PCC Rain Water Spout including cutting of concrete, fixing in position with (1:4) cement sand mortar, complete in all respect as directed by Engineer Incharge. a. 6" Wide (Internal Size) Water Spout.	35	Each	2500/-	87,500/-
5	CONCRETE CORE CUTTING Providing & cutting core in rcc walls of any thickness as per direction by the Engineer Incharge	6	Each	7000/-	42,000/-
Total					1,653,708/-
13% SST					214,982.04
Grand Total with SST					1,868,690.04/-

Note:

The product will be applied by the nominated or authorized applicator and a minimum of 5 years of warranty shall be given by manufacturer. The contractor's performance guarantee shall be released after the completion of two rainy seasons.

Grand Total Amount Rupees in Words: Rs. One Million Eight Hundred Sixty Eight Thousand Six Hundred Ninty Rupees & Zero Four Paise Only/-.

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

M. HARIQ QURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi

DR. SHARID MIR
Chairman - PC
Assistant Professor - Management
IBA Karachi



Stamp & Signature