

GIRLS HOSTEL PARTITION WALL AT IN GYMNASIUM ROOM

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	PARTITION WALL				
	Providing and fixing wooden partition wall framing of partition wall would be at an interval of 2'x2.5' height up to 8' and strengthen it with ceiling (which has a 14' height) by adding vertical wooden member section of wood 2"x 3" red meranti wood for framing with perfect termite proofing, and fixed over it lasani laminated sheet on both sides all tools & plants and folding also included into it as per approved plan. complete in all respect as per the instruction of Engineer. note: vertical support not measured saparety.	510	sft		
2	DOOR FRAME AND SHUTTERS				
	door frame of same wood in section of 3"x4" provided and fixing in partion wall and door shutter would be the same laminated lasani sheet of partition wall, lock , tower bolt , handle and door closer will also be fixed there . Complete all work as per instruction of Enginee.in all doors	192	sft		
3	ALUMINIUM SHEET				
	Providing and fixing Aluminium plan sheet 6" high which fixed both side of the partition wall's bottom, colour of sheet should be as per instruction of Engineer. Complete in all respect as per instruction of Engineer	180	rft		